

Notice dated 25th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to 2 P.M., on 25th February 1928, for restoring Somenahalli Votikere, minor tank of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 75 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Somenahalli Votikere minor tank, Malur Taluks in default of which, tender" will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Item of works	Per	Quantity	Rate	Cost	Total
Earthwork to bund watering and tamping ...	C.yd.	1,275	Rs. a. p.	Rs.	Rs.
Turfing to bund ...	S.yd.	1,149			
Removing and resetting the old stone work with new jelly wherever necessary.	C.yd.	61			
New stone work ...	"	195			
Fixing new grave stones with numbering and figuring etc., complete.	No.	8			
Index stones ...	"	8			
Register number stone ...	"	1			
Figuring and numbering in available stones ...	"	2			
Gauge stone complete ...	"	1			
Removing jungle and prickly piers ...	Lump	sum			
Removing the old loose earth over the top to a depth of 1' ...	Lump	sum			
Total cost per bund ...	...	...			
<i>Sluice at 45'50.</i>					
Earthwork excavation ...	C.yd.	45			
Refilling the same ...	"	45			
Surki concrete ...	C.ft.	206			
Burnt brick in surki mortar ...	"	402			
Burnt stone slabs 6" thick ...	S.ft.	193			
Surki mortar plastering ...	Sqr.	3'09			
Providing wooden plug with rod and locking arrangement.	Lump	sum			
Drilling holes for cross and orifice slabs ...	No.	L. S.			
Filling up the old sluice gap with good earth tamping, etc., complete.	Lump	sum			
Total sluice ...	...	...			

Items of work		Per	Quantity	Rate	Cost	Total
<i>Waste Weir.</i>				Rs. a. p.	Rs.	Rs.
Earthwork excavation	...	C.yd.	7			
Earthwork to bund	...	"	100			
Surki concrete	...	C.ft.	93			
Benching and chistling rock	...	Lump	sum			
Brick in surki mortar	...	C.ft.	125			
Burnt stone slabs 6" thick	...	S.ft.	134			
Plastering with surki mortar	..	Sqr.	7'20			
New stone work	...	C.yd.	57			
Total for weir	...	...	..	...	...	...
Total of all	...	...	...	...	...	...
Contingencies	...	...	...	...	...	...
Grand Total	...	...	...	...	..	...

Notice dated 25th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 28th February 1928, for restoring Mattikunte Uramundinakere Tank. Register No. 350—728 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 150 (rupees one hundred and fifty only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Mattikunte Uramundinakere Tank, Kolar Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be furnished in words as well as in figures.

Items of work	Per	Quantity	Rate	Cost	Total
<i>Bund.</i>					
Earthwork to bund watering and tamping	C.yd.	6,612	Rs. a. p.	Rs.	Rs.
Turfing to bund	S.yd.	5,000			
New stone pitching	C.yd.	547			
Fixing grade stones with numbering, etc., complete.	No.	23			
Index stones	"	23			
B. M. Stones	"	2			
Reg. No. and date stone	"	1			
Gauge stone	"	1			
Clearing of jungle	L. S.	...			
Total for bund	...	...	...	...	...
<i>Sluice at R. L. 45'00.</i>					
Earthwork excavation	C.yd.	18			
Refilling the same	"	18			
Surki concrete	C.ft.	254			
Burnt brick in surki mortar	"	171			
Burnt stone slabs 6" thick	S.ft.	169			
Plastering with surki mortar	Sqrs.	2.78			
Providing wooden plug with rod and locking arrangement.	L. S.	...			
Drilling holes	No.	3			
Total for sluice	...	...	...	...	...
<i>Weir.</i>					
Earthwork excavation	C.yd.	284			
Surki concrete	C.ft.	250			
Burnt brick in surki mortar	"	557			
Burnt stone slabs 4" to 6" thick	S.ft.	404			
Plastering with surki mortar	Sqr.	7.69			
New stone work for apron	C.yd.	126			
Providing joggles	Each	7			
Total for weir	...	...	...	...	...
Total	...	...	...	...	...
Contingencies	...	...	...	...	...
Grand Total	...	...	...	...	...

Notice dated 7th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. on 27th February 1928, for restoring Korgondanahalli Melinkere tank, R. No. 629-781 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees Two hundred and fifty only (250) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Korgondanalalli Melinkere Tank, Kolar Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Items of work	Per	Quantity	Rate	Cost	Total
BUND.			Rs. a. p.	Rs.	
Earthwork to bund, watering and tamping	C.dy.	5,461			
Turfing	S.yd.	2 522			
Gravel backing	C.yd.	284			
Removing and resetting old stone with new jelley wherever necessary.	L. S.	...			
New stone work	C.yd.	750			
Preparing and fixing new grade stones with cutting figures and painting.	Each	18			
Preparing and fixing Index stones	"	18			
Do Reg. No. and date stone	"	1			
Do B. M. stones	"	2			
Do Gauge stone	"	1			
Clearing jungle	Grade	12			
Clearing sand and loose soil	C.yd.	415			
Puddle wall	"	240			
Total bund	...	...	...	...	...
SLUICE.					
Repairing the existing sluice	L. S.	..			
WASTE WEIR.					
Earthwork excavation	C.yd.	423			
Surki concrete	C.ft.	571			
Burnt brick in Surki mortar	C.ft.	663			
Burnt stone slabs 6" thick	S.ft.	799			
Pin slabs (3' x 2')	Each	26			
Tongue and groove joints	"	25			
Surki plastering	Sqr.	12.19			
New stone work	C.yd.	244			
Total waste weir	...	...	...	...	...
Total bund, sluice and waste weir	...	...	...	...	...
Contingencies	L. S.	...	...	...	...
Grand Total	...	...	...	...	...

Notice dated 22nd January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 28th February 1928, for restoring Venkatapur tank, R. No. 207 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 2 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Venkatapur Tank, Kolar Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The quotations should be noted in words as well as in figures:—

Items of work	Per	Rate	Quantity	Cost	Total
<i>Bund at R. L. 54.50 top width 4½ feet.</i>					
Earthwork to bund including watering and tamping.	C.yds.		3,892		
Turfing	Sqr.		4,111		
Cutting trenches in old bund for seat of new earth	Each		17		
	Grade				
Providing new grade stones with index stones including cutting figures and painting.	Each		18		
Providing new Register No. Stone with painting, etc., complete.	"		1		
Providing new date stone with painting, etc., complete.	"		1		
Providing new gauge stone with painting, etc., complete.	"		1		
Providing new inscription stone with painting, etc., complete.	"		1		
Clearing jungle and cutting trees with roots	Lump sum		...		
New stone work	C.yd.		765		
Removing and resetting old stone with jelly	"		189		
Total	...		..		
<i>Sluice.</i>					
Repairing the existing sluice and constructing front and rear cisterns with locking arrangements.	Lump sum		...		
Total	...		...		
<i>Waste wire at the right end of R. L. 50.00.</i>					
Earthwork excavation	C.yd.		98		
Concrete in surki mortar	C.ft.		231		
Burnt brick in surki mortar	"		478		
Burnt stone slabs 6" thick	S.ft.		300		
Surkey mortar plastering	Sqr.		6.37		
Providing joggles	Each		10		
New stone work	C.yd.		55		
Clearing site, approaches, boulders, etc.	Lump sum		...		
Total	...		...		
Total of bund, sluice and weir	...		...		
Cantingencies	...		..		
Grand total	...		...		